

LEGEND

(E) CONSTRUCTION TO REMAIN. G.C. TO PATCH AND REPAIR AS REQUIRED TO "LIKE-NEW" CONDITION.

NEW PARTITION

EXISTING DOOR & FRAME

NEW DOOR & FRAME

#

DOOR NUMBER, SEE SHEET A9.02 FOR DOOR SCHEDULE

PT-#

FINISH, SEE SHEET A9.01 FOR FINISH SCHEDULE

#

PARTITION TYPE, SEE SHEET A8.03

14/50

RECEPTACLE, SEE DETAIL 12/A8.02a & ELECTRICAL DRAWINGS

WALL CONNECTOR, V.I.F. EXACT LOCATIONS WITH TESLA. SEE DETAIL 8/A8.02a & ELECTRICAL DRAWINGS.

H.B.

HOSE BIBB

FLOOR TRANSITION, SEE SHEET A8.04 FOR FLOOR TRANSITION DETAILS

KEY NOTES

1

-1/2" MAX DELTA BETWEEN TOP OF F.F. AND TOP OF ADJACENT EXTERIOR SURFACE

2

DUPLEX OUTLETS ON COLUMNS AT 4'-3" A.F.F., SEE ELECTRICAL DRAWINGS.

3

NEW FOOTINGS FOR LIFTS. SEE STRUCTURAL.

4

BOLLARD, SEE DETAIL 7/A8.02

5

4' HIGH COLUMN WRAP IN RED SEE A2.02 FOR WRAP SPEC.

6

CLEAN AND REFURBISH (E) STOREFRONT OR (E) DOOR TO LIKE "NEW-CONDITION", TYP.

7

1/8" PER FEET SLOPE AWAY FROM BUILDING, TYP. U.O.N

8

CORNER GUARD, SEE DETAIL 3/A8.01

9

ELECTRICAL PANEL/TRANSFORMER/CT CABINET, SEE ELECTRICAL DRAWING FOR MORE INFO. GC TO FIELD VERIFY DEPTH OF EQUIPMENT PRIOR TO INSTALLING BOLLARD(S) TO ENSURE CODE COMPLIANT CLEARANCE IS PROVIDED IN FRONT OF EQUIPMENT.

10

WINDOW FILM. SEE BUILDING ELEVATIONS.

CAL GREEN NOTES

ALL CONTRACTORS, SUB CONTRACTORS AND MATERIAL SUPPLIERS ARE TO GO TO SHEETS T1.1-T1.4 (CAL GREEN CHECKLIST SHEETS) TO MAKE SURE THAT THEY ARE FOLLOWING ALL REQUIRED MEASURES AND REQUIREMENTS DURING ALL PHASES OF CONSTRUCTION OF THIS PROJECT.

City of Santa Rosa

Planning & Economic Development Department

12/12/2022

RECEIVED

NOTE: CARPET AND CARPET TILE TO BE SECURELY ATTACHED AND HAVE A FIRM CUSHION PAD, OR BACKING (OR NO CUSHION OR PAD). CARPET AND CARPET TILE SHALL HAVE A LEVEL LOOP, TEXTURED LOOP, LEVEL CUT PILE, LEVEL CUT/UNCUT PILE TEXTURE. PILE HEIGHT SHALL BE 1/2 INCH MAXIMUM. EXPOSED EDGES OF CARPET SHALL BE FASTENED TO FLOOR SURFACES AND SHALL HAVE TRIM ON THE ENTIRE LENGTH OF THE EXPOSED EDGE. CARPET EDGE TRIM SHALL COMPLY WITH CBC SECTION 11B-303. (CBC 11B-302.2)

Rooms and Specifications:

- OFFICE 101: WALLS: PT-2, FLOOR: CPT-5, BASE: VB-1
- IT CLOSET 102: WALLS: PT-2, FLOOR: VT-1A, BASE: VB-1
- BREAK ROOM 104: WALLS: PT-2, FLOOR: SC-1, BASE: VB-1
- CUSTOMER LOUNGE 105: WALLS: PT-2, FLOOR: CPT-5, BASE: VB-1
- CONFERENCE ROOM 103: WALLS: PT-2, FLOOR: CPT-5, BASE: VB-1
- CONFERENCE ROOM 106: WALLS: PT-2, FLOOR: CPT-5, BASE: VB-1
- UNISEX TOILET 107: WALLS: PT-2, CT-5, CT-5G, FLOOR: CT-4, CT-4G, BASE: CT-4, CT-4G
- UNISEX TOILET 108: WALLS: PT-2, CT-5, CT-5G, FLOOR: CT-4, CT-4G, BASE: CT-4, CT-4G
- MEN'S TOILET 109: WALLS: PT-2, FRP-1, FLOOR: VT-1, BASE: VB-1
- WOMEN'S TOILET 110: WALLS: PT-2, FRP-1, FLOOR: VT-1, BASE: VB-1
- GALLERY 100: WALLS: PT-2, PT-3, FLOOR: CT-4, CT-4G, BASE: WB-1
- PARTS AND STOR. 116: WALLS: PT-2, FLOOR: SC-1, BASE: AT GYP BD ONLY, VB-1
- JANITOR CLOSET 114: WALLS: PT-2, FLOOR: SC-1, BASE: VB-1
- ELECT. CLOSET 115: WALLS: EXISTING, FLOOR: EXISTING, BASE: EXISTING
- WASH BAY 113: WALLS: FRP-1 AND PT-2, FLOOR: SC-2, BASE: VB-1, AT GYP. BD. ONLY
- SERVICE AREA 111: WALLS: PT-2, FLOOR: SC-1, BASE: VB-1, AT GYP BD ONLY
- COMPRESSOR RM 112: WALLS: PT-2, FLOOR: SC-1, BASE: VB-1

© COPYRIGHT 2019 TESLA MOTORS, INC. ALL RIGHTS RESERVED. PROPRIETARY AND CONFIDENTIAL BUSINESS INFORMATION

10/21/22

ARCVISION

INCORPORATED

ARCHITECTURE • ENGINEERING • STORE PLANNING

SAINT LOUIS / DALLAS / LAS VEGAS / ORLANDO

1950 CRAG ROAD, SUITE 300 ST. LOUIS, MO 63146

PH. (314) 415-2400 FAX (314) 415-2300 www.arcv.com

TESLA
FACILITY
3286 AIRWAY DRIVE
SANTA ROSA, CA 95403

ISSUE / REVISION	
04.06.22	75% ISSUE SET
04.18.22	100% ISSUE SET
07.15.22	△ CITY COMMENTS
08.29.22	△ CITY COMMENTS
09.16.22	△ OWNER COMMENTS
10.14.22	△ OWNER COMMENTS

DRAWING TITLE

CONSTRUCTION
& FINISH PLAN

SCALE: AS NOTED
PROJECT NUMBER: 220121
TESLA ID: 20585

SHEET NUMBER

A2.01

CONSTRUCTION FLOOR PLAN

SCALE: 3/32" = 1'-0"

1