

NOT FOR
CONSTRUCTION

90% SUBMITTAL

CONTRACT No. C00714

JANUARY 15, 2025


LOCATION MAPS



N.T.S.



N.T.S.



GENERAL NOTES

1. **STANDARDS:** ALL WORKMANSHIP, MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE CITY OF SANTA ROSA STANDARD PLANS, THE CONSTRUCTION SPECIFICATIONS FOR PUBLIC IMPROVEMENTS, THE SPECIAL PROVISIONS FOR THIS PROJECT AND THE STATE STANDARD SPECIFICATIONS AND STANDARD PLANS. THE CONTRACTOR IS RESPONSIBLE FOR UNDERSTANDING ALL STANDARDS PERTAINING TO THIS PROJECT.

2. **COMPOSITE BASE SHEET:** THE PROPOSED IMPROVEMENTS SHOWN ON THESE DRAWINGS ARE SUPERIMPOSED ON A BASE SHEET COMPOSED OF BOUNDARY, TOPOGRAPHIC, AND UNDERGROUND UTILITY INFORMATION PROVIDED BY CITY OF SANTA ROSA. THIS BASE SHEET INFORMATION IS SHOWN IN HALF TONE ON THE PLANS, THE LANDSCAPE ARCHITECT SHALL NOT BE HELD LIABLE FOR CHANGES, INACCURACIES, OMISSIONS, OR OTHER ERRORS ON THESE BASE SHEETS. THE COMPOSITE BASE SHEET IS PROVIDED AS AN AID ONLY AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR REVIEWING THESE DOCUMENTS AND INCORPORATING/INTEGRATING ALL CONSTRUCTION AS REQUIRED TO ACCOMMODATE SAME.

THE BASE SHEET SOURCE FOR THESE DRAWINGS IS:

'TOPOGRAPHIC MAP OF TENNIS COURT RESURFACING OF HOWARTH PARK AND GALVIN PARK', PREPARED BY CITY OF SANTA ROSA, (707) 543-3288, DATED 4/16/2024.

3. FIELD CONDITIONS: FIELD CONDITIONS MAY VARY FROM THE INFORMATION SHOWN ON THE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING FIELD CONDITIONS AND FOR REVIEWING DISCREPANCIES WITH THE CITY'S REPRESENTATIVE. THE CITY AND CITY'S REPRESENTATIVE ASSUME NO RESPONSIBILITY FOR FIELD CONDITIONS AND REQUIRED MODIFICATIONS.

4. **EXCAVATION:** THE CONTRACTOR SHALL CALL UNDERGROUND SERVICE ALERT (USA) AT 1-800-227-2600 NO LESS THAN 2 WORKING DAYS PRIOR TO ANY EXCAVATION FOR MARK OUTS OF EXISTING UNDERGROUND FACILITIES IN ACCORDANCE WITH SECTION 5-1.36E OF THE SPECIAL PROVISIONS. EXCAVATION IS DEFINED AS BEING 18 OR MORE INCHES IN DEPTH BELOW THE EXISTING SURFACE.

5. UTILITIES: THE LOCATIONS OF UNDERGROUND UTILITIES AND OTHER OBSTACLES SHOWN ON THE PLANS ARE BASED ON THE BEST AVAILABLE INFORMATION. THE CONTRACTOR SHALL POthOLE AND DETERMINE THE EXACT LOCATION OF ALL POTENTIAL CONFLICTS IN ACCORDANCE WITH U.S.A. LAWS AND THESE SPECIAL PROVISIONS AND THE STANDARD SPECIFICATIONS. IF ANY UNMARKED UTILITIES ARE ENCOUNTERED, OR IF UNABLE TO LOCATE A MARKED UTILITY AFTER POT HOLING, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER OF THAT UTILITY AND THE CITY'S REPRESENTATIVE.

THE CITY'S REPRESENTATIVE ASSUMES NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF DELINEATION OF UNDERGROUND UTILITIES, NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS OR UTILITIES WHICH ARE NOT SHOWN ON THESE DRAWINGS.

6. **CITY MONUMENTS:** THE CONTRACTOR SHALL PROTECT AND PRESERVE CITY MONUMENTS. THE CONTRACTOR SHALL COORDINATE WITH THE CITY'S REPRESENTATIVE 10 WORKING DAYS IN ADVANCE FOR REFERENCING OF EXISTING MONUMENTS TO BE DISTURBED. THE CONTRACTOR SHALL RECONSTRUCT DISTURBED MONUMENTS IN ACCORDANCE WITH CITY STANDARD-280.

7. OVERHEAD UTILITIES: OVERHEAD UTILITY SERVICE DROPS ARE NOT SHOWN ON THE PLANS. THE CONTRACTOR SHALL INVESTIGATE THE SITE AND BE AWARE OF LIMITED CLEARANCES UNDER OVERHEAD UTILITY LINES AND LOW HANGING TREE BRANCHES. THE CONTRACTOR'S TRUCKS AND EXCAVATION EQUIPMENT SHALL BE SIZED SO THAT OVERHEAD WIRES AND TREE BRANCHES ARE NOT DAMAGED.

8. DISPOSAL: ALL EXCAVATED MATERIAL SHALL BE DISPOSED OF AS GENERATED AND AT NO TIME SHALL THE CONTRACTOR PLACE EXCAVATED MATERIAL AT THE WORK SITE.

9. TREE PROTECTION AND MAINTENANCE REQUIREMENTS: SHALL BE PER TREE PROTECTION NOTES, SHEET L3.2. THE CONTRACTOR SHALL ONLY REMOVE EXISTING TREES OR SHRUBS AS NOTED ON THE PLANS OR AS DIRECTED BY THE CITY'S REPRESENTATIVE.

INDEX TO SHEETS

<u>SHEET NO.</u>	<u>TITLE</u>	<u>PAGE #</u>
<u>LANDSCAPE DRAWINGS</u>		
L1.0	COVER SHEET	1
L2.0	EXISTING CONDITIONS PLAN	2
L3.0-L3.1	DEMOLITION AND EROSION CONTROL PLAN	3-4
L4.0	GRADING AND DRAINAGE PLAN	5
L5.0	SITE CONSTRUCTION PLAN	6
L6.0	IRRIGATION PLAN	7
L6.1	LANDSCAPE DOCUMENTATION	8
L7.0	PLANTING PLAN	9
H8.0-H8.4	CONSTRUCTION DETAILS	10-14
<u>STRUCTURAL DRAWINGS</u>		
S0.1	STRUCTURAL TYPICAL NOTES AND DETAIL	15

PROJECT DIRECTORY

CLIENT

CITY OF SANTA ROSA
CONTACT: SCOTT WILKINSON
RECREATION AND PARKS
55 STONY POINT ROAD
SANTA ROSA, CA 95401
PHONE: (707) 543-3953

CONTACT: DANNY CHEN
TRANSPORTATION AND PUBLIC WORKS
69 STONY CIRCLE
SANTA ROSA, CA 95401
PHONE: (707) 543-3911

GEOTECHNICAL ENGINEER

RGH CONSULTANTS
CONTACT: ERIC CHASE
3501 INDUSTRIAL DRIVE, SUITE A
SANTA ROSA, CA 95403
PHONE: (707) 544-0188

LANDSCAPE ARCHITECT/PRIME CONSULTANT

CALLANDER ASSOCIATES
CONTACT: NATE RITCHIE
1633 BAYSHORE HIGHWAY, SUITE 133
BURLINGAME, CA 94010
PHONE: (650) 375-1313

TOPOGRAPHIC SURVEY & STAKING

SURVEY DIVISION
CONTACT: WALT OLAWSKI
SANTA ROSA TRANSPORTATION & PUBLIC WORKS
69 STONY CIRCLE
SANTA ROSA, CA 95401
PHONE: (707) 543-3851

STRUCTURAL ENGINEER

RW CONSULTING ENGINEERS
 CONTACT: DUSTIN HAYES
 1450 HARBOR BOULEVARD, SUITE F
 WEST SACRAMENTO, CA 95691
 PHONE: (916) 716-6910



L1.0

[illegible]

	FOUND IRON PIPE AS NOTED
	FOUND CENTERLINE MONUMENT, SIZE AS NOTED
	FOUND NAIL & TAG, STAMPED AS NOTED
	SET SURVEY CONTROL POINT AS NOTED
	BARRICADE - BOLLARD
	BIKE DETECT
	CABLE TV - MARKOUT
	CABLE TV - PULLBOX
	CABLE TV - SERVICE RISER
	ELECTRIC - PULLBOX
	ELECTRIC - JOINT POLE
	ELECTRIC - JOINT POLE WITH LIGHT
	ELECTRIC - JOINT POLE WITH RISER
	ELECTRIC - JOINT POLE WITH RISER & LIGHT
	ELECTRIC - GUY ANCHOR
	ELECTRIC - MARKOUT
	ELECTRIC - OVERHEAD WIRE
	ELECTRIC - CABINET
	ELECTRIC - METER
	ELECTRIC - SURFACE TRANSFORMER
	ELECTRIC - VAULT
	FENCE - CHAINLINK
	FENCE - WIRE
	FENCE - WOOD
	FENCE - GATE POST
	GAS - ETS
	GAS - MARKOUT
	GAS - METER
	GAS - VALVE
	GAS - VAULT
	MAILBOX
	ROADBOX
	SANITARY SEWER - CLEANOUT (MAIN)
	SANITARY SEWER - CLEANOUT (SERVICE)
	SANITARY SEWER - MANHOLE
	SANITARY SEWER - SCRIBBED "S" (SERVICE)
	SANITARY SEWER - MARKOUT
	SHRUB
	SIGN
	STREET LIGHT - STREET LIGHT
	STREET LIGHT - ELECTROLIER
	STREET LIGHT - MARKOUT
	STREET LIGHT - PULLBOX
	STORM DRAIN - CATCH BASIN
	STORM DRAIN - DROP INLET
	STORM DRAIN - MANHOLE
	SURFACE LIGHT
	STORM DRAIN - MARKOUT
	TELEPHONE - MANHOLE
	TELEPHONE - MARKOUT
	TELEPHONE - PULLBOX
	TELEPHONE - SERVICE RISER
	TELEPHONE - VAULT
	TREE - DRIP LINE
	TREE - PALM
	TRAFFIC SIGNAL - CABINET, CONTROL
	TRAFFIC SIGNAL - CABINET, SERVICE
	TRAFFIC SIGNAL - DETECTOR LOOP


DI	DROP INLET
DW	DASHED WHITE
DWY	DRIVEWAY
DY	DASHED YELLOW
EDGE	EDGE/CONCRETE BAND
ELEC.	ELECTRIC
EP	EDGE OF PAVEMENT
EVGRGN	EVERGREEN
F/C	FACE OF CURB
FDC	FIRE DEPARTMENT CONNECT
FEN	FENCE
FG	FINISH GRADE
FL	FIRE HYDRANT
FLH	FLOW LINE
FND	FOUND
GB	GRADE BREAK
GM	GAS METER
GV	GAS VALVE
HOPE	HIGH DENSITY POLYETHYLENE
HDWL	HEADWALL
IC	INTERCONNECT
INV	INVERT
I.P.	IRON PIPE
IRR	IRRIGATION
JB	JUNCTION BOX
JP	JOINT POLE
LIP	LIP OF GUTTER
MH	MANHOLE
M/O	MARKOUT
MON.	MONUMENT
NG	NATURAL GROUND
NT	NO TAG
OHW	OVERHEAD WIRE
PB	PULLBOX
PB_POST	PUSH BUTTON POST
PIV	POST INDICATOR VALVE
PVC	PVC PIPE
RPC	REINFORCED CONCRETE PIPE
RPM	RAISED PAVEMENT MARKER
RR	RAILROAD
RR	RISER
SERV.	SERVICE
SD	STORM DRAIN
SDMH	STORM DRAIN MANHOLE
SL	STREET LIGHT
SS	SANITARY SEWER
SSMH	SANITARY SEWER MANHOLE
S/W	SIDEWALK
SWL	SOLID WHITE LINE
SYL	SOLID YELLOW LINE
TB	TOP OF BANK
TC	TOP OF CURB
TEL	TELEPHONE
TFW	TOP FACE OF WALL
TG	TOP GRADE
TOE	TOE OF BANK OR SLOPE
TREE W	TREE WELL
T. PATCH	TRENCH PATCH

TS	TRAFFIC SIGNAL
UT	UTILITY TRENCH
VG	VALLEY GUTTER
VLT	VAULT
WM	WATER METER
WTR	WATER
WV	WATER VALVE
Y-Y	DOUBLE YELLOW
#xxx	STRUCTURE NUMBER

TS	TRAFFIC SIGNAL
UT	UTILITY TRENCH
VG	VALLEY GUTTER
VLT	VAULT
WM	WATER METER
WTR	WATER
WV	WATER VALVE
Y-Y	DOUBLE YELLOW
#xxx	STRUCTURE NUMBER


SOUTH 49° 06' 01" EAST BETWEEN CITY OF SANTA ROSA HORIZONTAL
CONTROL NETWORK COORDINATE MONUMENTS G-1008 & G-63.
NAD83 - ZONE 2 - EPOCH 2010.00

CITY OF SANTA ROSA VERTICAL CONTROL NETWORK BENCHMARK B-279.
ELEVATION = 231.16 FFEET (NGVD 29).



NOT FOR
CONSTRUCTION

City of
Santa Rosa

[illegible]

DATE: 1/15/2025
CHK BY: NR

AS SHOWN	DATE: 1
IC/DC	CHK BY:

APPROVED: Director - Engineering

By _____
Dan Hennessey

CITY OF SANTA ROSA
HOWARTH COURTS RENOVATION

EXISTING CONDITIONS PLAN

CONTRACT NO.
C00714

SHEET 2 OF 15
FILE NO. 2024-0014

L2.0

TREE PROTECTION NOTES

1.

CITY STANDARDS: TREE PROTECTION SHALL COMPLY WITH THE SPECIFICATIONS. WHERE CITY REQUIREMENTS CONFLICT WITH THE CONSTRUCTION DOCUMENTS, THE MORE STRINGENT REQUIREMENT SHALL APPLY.
2.

PROJECT STARTUP: PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL MEET ON-SITE WITH THE CITY'S REPRESENTATIVE TO REVIEW ALL WORK PROCEDURES, ACCESS ROUTES, STORAGE AREAS, AND TREE PROTECTION MEASURES.
3.

ROOT PROTECTION ZONE: ROOT PROTECTION ZONES SHOWN ON THE PLANS ARE APPROXIMATE. VERIFY IN FIELD. THE ROOT PROTECTION ZONE (RPZ) SHALL BE REGARDED AS THE AREA BENEATH A TREE'S CANOPY, OR EXTENDING FROM THE FACE OF THE TRUNK TO TEN (10) TIMES THE TREE'S DIAMETER AT BREAST HEIGHT (DBH), WHICHEVER IS GREATER. THERE SHALL BE NO DUMPING, WASHING OUT, OR STORAGE OF EQUIPMENT OR MATERIALS WITHIN THE RPZ OF ANY TREE. WORK WITHIN THE RPZ SHALL BE PERFORMED BY HAND, INCLUDING CLEAR AND GRUBBING.
4.

TREE PROTECTION FENCING: ROOT PROTECTION ZONES SHALL BE FENCED ACCORDING TO TREE PROTECTION DETAIL IN THE LOCATIONS SHOWN ON THE PLANS. FENCING SHALL BE ERECTED PRIOR TO ANY DEMOLITION OR CONSTRUCTION ON SITE AND SHALL NOT BE REMOVED OR MODIFIED BEFORE PROJECT COMPLETION WITHOUT AUTHORIZATION FROM THE CITY'S REPRESENTATIVE. FENCING MAY BE INSTALLED IN A SINGLE RUN AROUND MULTIPLE TREES.
- 4.1.

TREE PROTECTION MEASURES SHALL NOT BE MODIFIED TO FACILITATE CONSTRUCTION ACTIVITIES, EXCEPT WITH PRIOR REVIEW AND APPROVAL BY THE CITY'S REPRESENTATIVE.
5.

DEMOLITION: ALL EXISTING, UNUSED LINES OR PIPES BENEATH THE CANOPIES OF RETAINED TREES SHALL BE ABANDONED OR CUT OFF AT EXISTING SOIL GRADE.
6.

MAINTENANCE DURING CONSTRUCTION: APPLY A SIX INCH LAYER OF ARBOR MULCH WITHIN THE RPZ.
- 6.1.

ANY ACCUMULATED CONSTRUCTION DUST ON LIMBS OR FOLIAGE IS TO BE REMOVED WITH WATER PERIODICALLY OR AS DIRECTED BY THE CITY'S REPRESENTATIVE.
7.

TRENCHING AND GRADING: THERE SHALL BE NO TRENCHING OR GRADING WITHIN THE RPZ EXCEPT WITH PRIOR APPROVAL OF THE CITY'S REPRESENTATIVE. WHERE TRENCHING HAS BEEN APPROVED, FOLLOW THE PROCEDURE OUTLINED IN NOTE #8 BELOW. ANY EQUIPMENT USED SHALL BE OPERATED OUTSIDE THE RPZ.
- 7.1.

ALL UTILITIES, BOXES, METERS, VAULTS AND SERVICES ARE TO BE ROUTED BEYOND RPZ UNLESS SPECIFICALLY NOTED ON PLANS TO ROUTE WITHIN RPZ.
- 7.2.

ANY GRADE CHANGES OUTSIDE THE RPZ SHALL NOT SIGNIFICANTLY ALTER DRAINAGE TO OR FROM THE TREE. NO GRADING SHALL OCCUR WITHIN THE RPZ. IF GRADING CONFLICTS ARISE, NOTIFY THE CITY'S REPRESENTATIVE PRIOR TO COMMENCING ADJACENT GRADING OPERATIONS.
8.

ROOT CUTTING: PRIOR TO EXCAVATING WITHIN A RPZ, A TRENCH SHALL BE DUG ALONG THE EDGE OF THE EXCAVATION CLOSEST TO THE TREE TRUNK. THIS TRENCH SHALL BE DUG BY HAND OR WITH AN AIR SPADE TO A DEPTH OF 30 INCHES, AND SHALL BE OF A SUFFICIENT WIDTH TO MANUALLY SEVER ANY ROOTS ENCOUNTERED GREATER THAN 2" DIAMETER. CUTS SHALL BE MADE PERPENDICULAR TO THE DIRECTION OF THE ROOT'S GROWTH, USING A CLEAN HAND SAW. AFTER ROOTS ARE CLEANLY SEVERED, EXCAVATION EQUIPMENT MAY BE USED AS REQUIRED ON THE SIDE OF THE TRENCH FARTHEST FROM THE TREE.
- 8.1.


WITHIN ONE HOUR, CUT OR EXPOSED ROOTS SHALL BE COVERED WITH MOIST SOIL OR WITH BURLAP THAT IS KEPT WET UNTIL THE EXCAVATION CAN BE BACK-FILLED AND WATERED THOROUGHLY.
9.

SOIL PREPARATION: NO RIPPING OR ROTOTILLING SHALL OCCUR WITHIN THE RPZ, UNLESS APPROVED BY THE CITY'S REPRESENTATIVE.
10.

PLANTING AND IRRIGATION: NO PLANTING OR IRRIGATION SHALL BE INSTALLED WITHIN 6 FEET OF TRUNKS OF EXISTING TREES UNLESS OTHERWISE INDICATED ON PLANS. NEWLY PLANTED TREES SHALL BE IRRIGATED PER IRRIGATION DRAWINGS. MULCH SHALL NOT BE PLACED DIRECTLY AGAINST TRUNKS.
11.

PRUNING: AT NO TIME SHALL TREE LIMBS BE CUT BY CONSTRUCTION PERSONNEL. NO PRUNING SHALL TAKE PLACE EXCEPT AS DIRECTED BY THE CITY'S REPRESENTATIVE. WORK MUST BE PERFORMED BY A CERTIFIED ARBORIST IN ACCORDANCE WITH THE ISA TREE PRUNING GUIDELINES.
12.

DAMAGE: THE CONTRACTOR SHALL BE HELD LIABLE FOR ANY DAMAGE TO EXISTING TREES, I.E. TRUNK WOUNDS, BROKEN LIMBS, POURING OF ANY DELETERIOUS MATERIALS, OR CONCRETE WASHOUT UNDER THE DRIPLINE OF THE TREES. DAMAGES WILL BE ASSESSED USING THE "GUIDE TO PLANT APPRAISAL" 9TH EDITION, PUBLISHED BY THE INTERNATIONAL SOCIETY OF ARBORICULTURE. ANY DAMAGE OR INJURY TO TREES DURING CONSTRUCTION SHALL BE REPORTED TO THE CITY'S REPRESENTATIVE IMMEDIATELY SO THAT REMEDIAL ACTION CAN BE TAKEN.



DEMOLITION LEGEND

	CLEAR AND GRUB
	REMOVE AND DISPOSE OF EXISTING COURT SURFACING, ASPHALT, AND A PORTION OF THE UNDERLYING BASE ROCK TO ACCOMMODATE THE NEW COURT PAVEMENT SECTION.
	EXISTING TREE TO REMAIN, PROTECT IN PLACE AND INSTALL TREE PROTECTION FENCING WHERE SHOWN ON PLAN
	REMOVE AND DISPOSE OF ITEM
	CONSTRUCTION FENCING, PER SPECS.
	TREE PROTECTION FENCING
T.R.	TO REMAIN, PROTECT IN PLACE
T.B.R.	TO BE REMOVED AND DISPOSED OF

EROSION CONTROL LEGEND

	STORM DRAIN INLET PROTECTION
	CONSTRUCTION ACCESS ROUTE

DEMOLITION KEY NOTES

CODE	DESCRIPTION
D-101	NET POST AND ASSOCIATED FOOTINGS, T.B.R.
D-103	CENTER ANCHOR TIE DOWN AND ASSOCIATED FOOTINGS, T.B.R.
D-105	EXISTING COURT NET, T.B.R.
D-108	COURT LIGHTING, T.R.
D-109	PERIMETER CHAIN LINK FENCE, INCLUDING ASSOCIATED CONCRETE BAND AND FOOTINGS, T.R. EXCEPT IN LOCATIONS WHERE FENCE REPAIR IS INDICATED ON SITE CONSTRUCTION PLAN, OR REMOVAL IS REQUIRED FOR CONSTRUCTION ACCESS. RETURN ALL EXISTING SIGNAGE HUNG ON THE FENCE TO THE CITY.


DEMOLITION KEY NOTES CONTINUED

CODE	DESCRIPTION
D-113	CHAIN LINK GATE, T.R.
D-114	CHAIN LINK GATE MODIFICATION, SEE SITE CONSTRUCTION PLAN.
D-115	CONCRETE PAVEMENT, T.R.
D-116	BALL WALL, T.R.
D-117	BENCH, T.R.
D-119	SALVAGE BENCH AND RELOCATE PER SITE CONSTRUCTION PLAN.
D-122	DRINKING FOUNTAIN, T.R.
D-124	TRASH RECEPTACLE, T.R.
D-127	BULLETIN BOARD SIGN, T.R.
D-129	SHED, T.R.
D-130	UTILITY CABINET, T.R.
D-135	STORM DRAIN CATCH BASIN, T.R.
D-136	CONCRETE CURB, T.R.
D-137	SALVAGE LANDSCAPE BOULDER AND REINSTALL AFTER CONSTRUCTING IMPROVEMENTS. FOR BIDDING PURPOSES ASSUME 7 BOULDERS.
D-138	SCOREBOARD, T.R.

FOR DEMOLITION AND EROSION CONTROL NOTES SEE SHEET 4



NOT FOR CONSTRUCTION



NO.	DATE	REVISION	BY

DATE: 1/15/2025	CHK BY: NR	APPROVED: Director - Engineering
SCALE: AS SHOWN	DWN BY: IC/DC	By: Don Hennessey

CITY OF SANTA ROSA	DEMOLITION AND EROSION CONTROL PLAN
HOWARTH COURTS RENOVATION	

CONTRACT NO. C00714
SHEET 3 OF 15
FILE NO. 2024-0014

L3.0

DEMOLITION NOTES

1. **CLEAR AND GRUB:** CLEAR AND GRUB ALL EXISTING VEGETATION, UNLESS OTHERWISE INDICATED, AS REQUIRED FOR THE SITE CONSTRUCTION, IRRIGATION, AND PLANTING OPERATIONS. LIMITS OF CLEARING SHALL BE REVIEWED WITH THE CITY'S REPRESENTATIVE PRIOR TO COMMENCEMENT OF WORK. STRIP ALL ORGANIC MATTER TO A SUFFICIENT DEPTH TO COMPLETELY REMOVE SUCH MATERIAL.

REVIEW DEMOLITION, AND CLEARING AND GRUBBING REQUIREMENTS ON SITE WITH CITY'S REPRESENTATIVE PRIOR TO COMMENCING DEMOLITION OPERATIONS.

ALL DEMOLITION OPERATIONS WITHIN THE DRIP
LINE OF TREES SHALL CONFORM TO TREE
PROTECTION REQUIREMENTS.

EXISTING SITE FURNISHINGS AND IRRIGATION
EQUIPMENT TO BE REMOVED SHALL BE RETURNED
TO THE CITY UNLESS OTHERWISE SPECIFIED.

2. IRRIGATION EQUIPMENT: REFER TO THE IRRIGATION PLAN FOR DISPOSITION OF EXISTING IRRIGATION EQUIPMENT, AND OTHERWISE PROTECT IN PLACE.

PERFORM EXISTING IRRIGATION SYSTEM
VERIFICATION PRIOR TO COMMENCING
DEMOLITION. SEE IRRIGATION NOTES FOR
REQUIREMENTS.

3. WINDSCREEN REMOVAL: REMOVE ALL WINDSCREEN ON EXISTING FENCE SURROUNDING ALL COURTS. FOR BIDDING PURPOSES ASSUME 620 LINEAR FEET.

EROSION CONTROL NOTES

1. RAIN EVENT ACTION PLAN: CONTRACTOR MUST ENSURE THAT THE CONSTRUCTION SITE IS PREPARED PRIOR TO THE ONSET OF ANY STORM. A RAIN EVENT ACTION PLAN (REAP) MUST BE IMPLEMENTED TO PROTECT ALL EXPOSED PORTIONS OF THE SITE WITHIN 48 HOURS PRIOR TO ANY LIKELY PRECIPITATION EVENT. CONTRACTOR SHALL HAVE ALL EROSION AND SEDIMENT CONTROL MEASURES IN PLACE FOR CONSTRUCTION.

2. EROSION AND SEDIMENT CONTROL; ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED UNTIL DISTURBED AREAS ARE STABILIZED. CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE MADE TO MEET FIELD CONDITIONS ONLY WITH THE APPROVAL OF OR AT THE DIRECTION OF A REPRESENTATIVE OF THE CITY.

3. **FIELD CHANGES:** THIS PLAN MAY NOT COVER ALL THE SITUATIONS THAT ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS MAY BE MADE TO THE PLAN IN THE FIELD SUBJECT TO THE APPROVAL OF OR AT THE DIRECTION OF A REPRESENTATIVE OF THE CITY.

4. MAINTENANCE MEASURES: ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED WEEKLY DURING PERIODS OF HEAVY USAGE, BI-WEEKLY DURING PERIODS OF NORMAL USAGE AND BEFORE AND AFTER ALL STORM EVENTS TO ENSURE MEASURES ARE FUNCTIONING PROPERLY.

5. STABILIZED CONSTRUCTION ENTRANCE: THE CONTRACTOR SHALL INSTALL THE STABILIZED CONSTRUCTION ENTRANCE PRIOR TO COMMENCEMENT OF GRADING. LOCATION OF THE ENTRANCE MAY BE ADJUSTED BY THE CONTRACTOR TO FACILITATE GRADING OPERATIONS. ALL CONSTRUCTION TRAFFIC ENTERING THE PAVED ROAD MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCE.

6. ROAD AND TIRE CLEANING; ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AT THE END OF EACH WORKING DAY. ALL TRUCK TIRES SHALL BE CLEANED PROPERLY BEFORE LEAVING THE SITE.

7. TRENCHES: AFTER UTILITY TRENCHES ARE BACKFILLED AND COMPACTED, THE SURFACES OVER SUCH TRENCHES SHALL BE MOUNDED SLIGHTLY TO PREVENT CHANNELING OF WATER IN THE TRENCH AREA. CARE SHOULD BE EXERCISED TO PROVIDE FOR CROSS-FLOW AT FREQUENT INTERVALS.

8. CONTRACTOR RESPONSIBILITY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS INCURRED WITH ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURE MAINTENANCE THROUGHOUT THE DURATION OF THE PROJECT.

9. DAMAGED EROSION CONTROL DEVICES: DAMAGED EROSION CONTROL DEVICES SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AS SOON AS PRACTICAL AFTER THE DAMAGE OCCURS.

10. DAILY WATERING: DURING GRADING OPERATIONS THE SITE SHALL BE WATERED ON A DAILY BASIS TO MINIMIZE THE RELEASE OF DUST AND OTHER PARTICULATE MATTER.



1633 Bayshore Highway, Suite 13
Burlingame, CA 94010
T 650.375.1313
www.callanderassociates.com
CALA Project No. 24023

www.callanderassociates.com
CALA Project No. 24023

NOT FOR
CONSTRUCTION



City of
Santa Rosa



CITY OF SANTA ROSA HOWARTH COURTS RENOVATION		SCALE: AS SHOWN	DATE: 1/15/2025		
		DWN BY: IC/DC	CHK BY: NR		
DEMOLITION AND EROSION CONTROL PLAN		APPROVED: Director – Engineering			
		By _____ Date _____			
		Dan Hennessey			
		NO. _____			
		REVISION _____			
		BY _____			
CONTRACT NO. C00714					
SHEET 4 OF 15					
FILE NO. 2024-0014					

	PROPOSED CONTOUR: 1'-0" INTERVAL TYP. (EXISTING CONTOURS ARE SCREENED ON PLAN)
	PROPOSED SPOT ELEVATION (EXISTING SPOT ELEVATIONS ARE SCREENED ON PLAN)
	SPOT ELEVATION EQUAL TO EXISTING GRADE, FIELD VERIFY
	DIRECTION AND PERCENT SLOPE OF SHEET DRAINAGE
	FLUSH CONDITION
	BENCHMARK

1. GRADING AND DRAINAGE: ALL PROPOSED PAVING, CURBS, WALLS, AND PLANTING AREAS SHALL SMOOTHLY CONFORM TO EXISTING ADJACENT FEATURES TO REMAIN. PROVIDE POSITIVE DRAINAGE ON ALL PAVING AND THROUGHOUT ALL PLANTING AREAS. CONTRACTOR SHALL FLOOD PAVED AREAS UPON COMPLETION AND RECONSTRUCT ANY LOW SPOTS AS DIRECTED. PAVING SHALL HAVE A RUNNING SLOPE OF 4.9% MAXIMUM WITH A CROSS SLOPE OF 1% MINIMUM TO 2% MAXIMUM UNLESS OTHERWISE SHOWN ON PLANS.
2. TOPSOIL STOCKPILE: STRIP AND STOCKPILE NATIVE TOPSOIL IN AN AMOUNT SUFFICIENT TO INSTALL A 6" LAYER OF TOPSOIL IN ALL PROPOSED PLANTING AREAS. STOCKPILE LOCATION(S) TO BE DETERMINED DURING CONSTRUCTION.
3. TOPSOIL PLACEMENT: CROSS-RIP ALL ROUGH-GRADED PLANTING AREA SUBSOILS AS SPECIFIED PRIOR TO TOPSOIL PLACEMENT.
4. BACKFILL: EXCAVATED MATERIAL NOT SUITABLE FOR BACKFILLING SHALL BE REMOVED AND LEGALLY DISPOSED OF OFF-SITE.
5. GRADING: CONTRACTOR SHALL PERFORM ALL EARTHWORK AND GRADING PER GEOTECHNICAL ENGINEER'S RECOMMENDATIONS AND PROJECT SPECIFICATIONS.




L4.0

SITE CONSTRUCTION LEGEND



COURT PAVEMENT

2
H8.1



COURT PAVEMENT OVERLAY

1
H8.1



CHAIN LINK FENCE, 4' HIGH

4
H8.1



CHAIN LINK SINGLE GATE, 6'-8" HEIGHT

5
H8.1



CHAIN LINK SINGLE GATE, 4' HEIGHT

1
H8.2



GATE MODIFICATION

2
H8.2




CHAIN LINK FENCE REPAIR, SEE SITE CONSTRUCTION NOTE 1

3
H8.2



REPLACE EXISTING CHAIN LINK FENCE POST

3
H8.1



REINSTALL EXISTING BENCH

4
H8.2



PICKLEBALL NET POST

5
H8.2



TENNIS NET POST



CENTER ANCHOR TIE DOWN



PLANTING AREA




WINDSCREEN, PER SPECS



EQUAL

SITE CONSTRUCTION NOTES

1. CHAIN LINK FENCE REPAIR: REPAIR EXISTING 10'-0" TALL CHAIN LINK FENCE AT THE LOCATIONS SHOWN ON THE PLAN AND AS DIRECTED BY THE CITY. FOR BIDDING PURPOSES ASSUME REMOVAL AND REPLACEMENT OF 70 LINEAR FEET OF GALVANIZED CHAIN LINK FABRIC.
2. DIMENSIONS: ALL DIMENSIONS SHOWN SUPERSEDE SCALED DIMENSIONS. ALL DIMENSIONS ARE TO FACE OF CURB, EDGE OF CONCRETE FLATWORK/MOWBAND, OR CENTERLINE OF FENCE.
3. PROJECT STAKING: ALL PROPOSED SITE FEATURES SHALL BE STAKED IN FIELD BY THE CONTRACTOR FOR REVIEW BY THE CITY'S REPRESENTATIVE PRIOR TO CONSTRUCTION. ALL CURVES SHALL BE SMOOTH AND CONTINUOUS WITH CAREFULLY MATCHED TANGENTS.



CALA

1633 Bayshore Highway, Suite 133
Burlingame, CA 94010
T 650.375.1313
www.collanderassociates.com
CALA Project No. 24023

NOT FOR
CONSTRUCTION

City of
Santa Rosa



NO.	DATE	REVISION	BY

SCALE: AS SHOWN
DWN BY: IC/DC

DATE: 1/15/2025
CHK BY: NR

APPROVED: Director – Engineering
By: Dan Hennessey

Date: _____

CITY OF SANTA ROSA
HOWARTH COURTS RENOVATION
SITE CONSTRUCTION PLAN

CONTRACT NO.
CO0714

SHEET 6 OF 15

L5.0
FILE NO. 2024-0014

IRRIGATION LEGEND

- IN-LINE DRIP IRRIGATION, NETAFIM, TECHLINE CV DRIPLINE, 0.6 GPH EMITTER FLOW AND 18-INCH EMITTER SPACING. SPACE EMITTER LINE ROWS AT 18-INCHES ON CENTER. INSTALL ALL LINES AT GRADE AND COVER WITH MULCH PER PLANTING PLAN. USE ONLY NETAFIM DRIPLINE TECHLOCK FITTINGS.

6
H8.3
- DRIP REMOTE CONTROL ZONE KIT, TORO, 700DK-1-MF, WITH AN NDS SCH 80 PVC BALL VALVE UPSTREAM OF VALVE, REPLACE EXISTING VALVE UNLESS OTHERWISE INDICATED AS AN ADDITIONAL VALVE
ADDITIONAL VALVE THAT DOES NOT REPLACE EXISTING VALVE


2
H8.3
- SLEEVE, SCHEDULE 40 PVC, 2X PIPE DIAMETER, 2" MIN WHEN ONLY CONTROL WIRES
- LATERAL LINE, CLASS 200 PVC

4
H8.3
- DRIP HEADER, SCH 40 PVC, SIZE PER PLAN
LATERAL / HEADER CONNECTION

5
H8.3
- CONTROL WIRES, DIRECT BURIAL TYPE, 1 FOOT MIN. DEPTH, INSTALL IN CONDUIT UNDER PAVEMENT
- DRIP IRRIGATION INDICATOR, RAINBIRD, OPERIND


2
H8.4
- DRIP FLUSH VALVE, NETAFIM, TISOV

1
H8.4
- VALVE NUMBER FOR DRIP AREA
- CONTROLLER EXPANSION, INSTALL NEW WEATHERTRAK WTPRO-6STA-KEY MODULE ON EXISTING WEATHERTRAK PRO CONTROLLER TO UPGRADE FROM 12 STATIONS TO 18 STATIONS



EXISTING COMPONENTS

- BACKFLOW PREVENTER, WATTS, 4" SIZE
- MAINLINE, SIZE PER PLAN
- REMOTE CONTROL VALVE
EXISTING VALVE NUMBER



IRRIGATION NOTES

1. SPECIFICATIONS: SEE IRRIGATION SPECIFICATIONS FOR ADDITIONAL INFORMATION.

2. VERIFICATION: SYSTEM DESIGN IS BASED ON 88 P.S.I AND 8 G.P.M. AVAILABLE AT THE POINT OF CONNECTION. CONTRACTOR SHALL VERIFY SAME AND NOTIFY LANDSCAPE ARCHITECT IF SUCH DATA ADVERSELY AFFECTS THE OPERATION OF THE SYSTEM. SUCH NOTICE SHALL BE MADE IN WRITING AND PRIOR TO COMMENCING ANY IRRIGATION WORK.

3. UTILITIES: CONTRACTOR SHALL VERIFY LOCATION OF ALL ON-SITE UTILITIES. RESTORATION OF DAMAGED UTILITIES SHALL BE MADE AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.

4. SCHEMATIC: SYSTEM FEATURES ARE SHOWN SCHEMATICALLY FOR GRAPHIC CLARITY. INSTALL ALL PIPING AND VALVES IN COMMON TRENCHES WHERE FEASIBLE AND INSIDE PLANTING AREAS WHENEVER POSSIBLE. ALL VALVES SHALL BE LOCATED IN GROUND COVER OR SHRUB AREAS WHENEVER POSSIBLE.

5. CODES AND MANUFACTURER'S SPECIFICATIONS: IRRIGATION SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL HEALTH CODES AND MANUFACTURER'S SPECIFICATIONS. NOTIFY CITY'S REPRESENTATIVE IF SITE CONDITIONS OR INFORMATION IN THE PROJECT PLANS AND SPECIFICATIONS ARE IN CONFLICT WITH THESE REQUIREMENTS.


6. SLEEVING: CONTRACTOR SHALL SIZE ALL SLEEVES TO BE A MINIMUM TWO TIMES THE SIZE OF THE INTERIOR PIPE. SLEEVES SHALL BE INSTALLED AT THE NECESSARY DEPTHS PRIOR TO PAVEMENT CONSTRUCTION. SLEEVING SHALL EXTEND 1'-0" FROM EDGE OF PAVEMENT INTO LAWN OR PLANTING AREA, AND SHALL HAVE ENDS CLEARLY MARKED ABOVE GRADE.

7. HEAD ALLOWANCE: CONTRACTOR SHALL ALLOW IN BID PRICE AN AMOUNT SUFFICIENT TO PROVIDE AND INSTALL AN ADDITIONAL 50 FEET OF DRIPLINE TO ACCOMMODATE FIELD
- CHANGES, EQUIPMENT SHALL BE LOCATED AS DIRECTED BY THE CITY'S REPRESENTATIVE. CONTRACTOR SHALL DELIVER TO THE CITY ANY UN-USED ADDITIONAL DRIPLINE AT THE END OF THE MAINTENANCE PERIOD.


8. MAINTAINING EXISTING IRRIGATION: SHOULD THE EXISTING MAINLINE BREAK OR BE SHUT OFF FOR ANY REASON DURING THE COURSE OF CONSTRUCTION THE CONTRACTOR SHALL HAND WATER ALL TREES, SHRUBS, TURF, AND GROUND COVER THAT THE EXISTING IRRIGATION SYSTEM WATERS. THE CONTRACTOR SHALL CONTINUE TO DO SO UNTIL THE IRRIGATION SYSTEM IS OPERABLE.

9. EXISTING IRRIGATION VERIFICATION: REVIEW THE LAYOUT OF THE EXISTING IRRIGATION SYSTEM WITH THE CITY'S REPRESENTATIVE TO CONFIRM OPERATIONAL STATUS OF ALL ZONES NEAR THE WORK AREA PRIOR TO COMMENCING DEMOLITION AND IRRIGATION WORK. VERIFY LIMITS OF EXISTING VALVE ZONES AND CONFIRM FIELD CONDITIONS MATCH WHAT IS SHOWN ON THE PLANS. REPORT ANY DISCREPANCIES AND NON-FUNCTIONAL COMPONENTS TO THE CITY'S REPRESENTATIVE IN WRITING.

10. POST-CONSTRUCTION OPERATIONAL TEST: REVIEW THE FUNCTIONALITY OF THE IRRIGATION SYSTEM (BOTH NEW AND EXISTING COMPONENTS) WITH THE CITY'S REPRESENTATIVE TO CONFIRM SUCCESSFUL OPERATION AFTER THE NEW SYSTEM COMPONENTS HAVE BEEN INSTALLED. CORRECT ANY DEFICIENCIES FOUND THAT WERE CAUSED TO THE EXISTING SYSTEM AS A RESULT OF CONSTRUCTION.



NOT FOR
CONSTRUCTION



NO.	DATE	REVISION	BY

SCALE: AS SHOWN	DATE: 1/15/2025
DWN BY: IC/DC	CHK BY: NR
APPROVED: Director – Engineering	
By _____ Date _____	
Don Hennessey	

CITY OF SANTA ROSA GALVIN COURTS RENOVATION	IRRIGATION PLAN	CONTRACT NO. C00714
		SHEET 7 OF 15
		FILE NO. 2024-0014

A. DATE: SEE TITLE BLOCK
B. PROJECT APPLICANT: CITY OF SANTA ROSA
C. PROJECT ADDRESS: 630 SUMMERFIELD RD, SANTA ROSA, CA 95405

1. ☒ PROJECT INFORMATION
2. ☒ WATER EFFICIENT LANDSCAPE WORKSHEET
3. ☐ *SOIL MANAGEMENT REPORT
4. ☒ LANDSCAPE DESIGN PLAN (SEE SHEET L7.0-L7.2)
5. ☒ IRRIGATION DESIGN PLAN (SEE SHEET L6.0-L6.2)
6. ☒ GRADING DESIGN (SEE SHEET L4.0-L4.2)
7. ☐ #CERTIFICATE OF COMPLETION
8. ☐ *CERTIFICATE OF INSTALLATION
9. ☐ *IRRIGATION SCHEDULE
10. ☐ *MAINTENANCE SCHEDULE
11. ☐ *LANDSCAPE IRRIGATION AUDIT

* CONTRACTOR IS RESPONSIBLE FOR COORDINATION OF IRRIGATION AUDIT BY THE LOCAL AGENCY, OR A THIRD PARTY CERTIFIED LANDSCAPE IRRIGATION AUDITOR. LANDSCAPE AUDITS SHALL NOT BE CONDUCTED BY THE PERSON WHO DESIGNED THE LANDSCAPE OR INSTALLED THE LANDSCAPE. CONTRACTOR IS RESPONSIBLE TO PAY FOR ALL ASSOCIATED FEES.

OWNER/CITY:
CITY OF SANTA ROSA
SCOTT WILKINSON
55 STONY POINT ROAD
SANTA ROSA, CA 9540
PHONE: (707) 543-3953

1. MWEO CODES AND REFERENCES: A COPY OF THE MODEL WATER EFFICIENT LANDSCAPE ORDINANCE (MWEO) DOCUMENT CAN BE FOUND AT WATER.CA.GOV. REFER TO MWEO SECTION 492.9 FOR CERTIFICATE OF COMPLETION REQUIREMENTS AND APPENDIX C FOR SAMPLE OF CERTIFICATE OF COMPLETION AND CERTIFICATE OF INSTALLATION FORM.
2. IRRIGATION PLAN CONTROLLER COPY: THE CONTRACTOR SHALL PLACE A LAMINATED 11X17 COPY OF THE IRRIGATION PLAN SHOWING THE HYDROZONES WITHIN THE IRRIGATION CONTROLLER(S) CABINET FOR FUTURE MANAGEMENT USE.

WATER EFFICIENT LANDSCAPE WORKSHEET									
This worksheet is filled out by the project applicant and it is a required element of the Landscape Documentation Package.									
Reference Evapotranspiration (ET _o)		42.0							
Hydrozone # /Planting Description ^a	Plant Factor (PF) ^f	Irrigation Method ^b	Irrigation Efficiency (IE) ^c	ETAF (PF/IE)	Landscape Area (sq. ft.)	ETAF x Area	Estimated Total Water Use (ETWU) ^d		
Regular Landscape Areas									
Low Water Use Plantings	0.2	Drip	0.81	0.25	3,975		981	25,558	
Totals					3,975	(A)	981	(B)	
Special Landscape Areas									
				1					
				1					
				1					
Totals					0	(C)	0	(D)	
ETWU Total								25,558	
Maximum Applied Water Allowance (MAWA) ^e								46,579	




City of
Santa Rosa

CITY OF SANTA ROSA GALVIN COURTS RENOVATION	SCALE: AS SHOWN	DATE: 1/15/2025			
	DWN BY: IC/DC	CHK BY: NR			
	APPROVED: <i>Director – Engineering</i>				
	By _____ Date _____ Don Hennessey				
LANDSCAPE DOCUMENTATION					
CONTRACT NO. C00714					
SHEET 8 OF 15					
FILE NO. 2024-0014					

 EXISTING TREE TO REMAIN




1. MULCH: INSTALL A UNIFORM THREE INCH COVERING OF MULCH IN ALL PLANTING AREAS, PER SPECIFICATIONS.
2. EXISTING PLANT MATERIAL: PROTECT ALL EXISTING PLANT MATERIAL AND TURF GRASS TO REMAIN. REPAIR ANY DAMAGES INCURRED AS A DIRECT RESULT OF THIS CONTRACT TO THE CITY'S SATISFACTION AT NO ADDITIONAL COST.
3. GROUND COVER: PROVIDE GROUND COVER AT INDICATED ON-CENTER SPACING THROUGHOUT ALL AREAS TO BE PLANTED. GROUND COVER SHALL BE PROVIDED UP TO THE WATERING BASIN OF ALL SHRUBS.
4. QUANTITIES: THE QUANTITIES SHOWN ON THE LABELS ARE NOT TO BE CONSTRUED AS THE COMPLETE AND ACCURATE LIMITS OF THE CONTRACT. FURNISH AND INSTALL ALL PLANTS SHOWN SCHEMATICALLY ON THE DRAWINGS.
5. TOP SOIL: ALL PLANTING AREAS TO RECEIVE A SIX INCH LAYER OF NATIVE TOP SOIL PER SPECIFICATIONS.
6. SOILS TESTING: SEE SPECIFICATIONS FOR TESTING OF TOP SOIL AND AMENDMENTS. CONTRACTOR SHALL ALLOW SUFFICIENT TIME FOR TESTING PRIOR TO CONSTRUCTION.



<u>CODE</u>	<u>BOTANICAL / COMMON NAME</u>	<u>SIZE</u>	<u>WATER USE</u>	<u>SPACING</u>
-------------	--------------------------------	-------------	------------------	----------------

		SHRUBS					
3 H8.4			JUN SKY	JUNIPERUS SCOPULORUM 'SKYROCKET' / SKYROCKET JUNIPER	15 GAL	LOW	48" o.c.
			PHO AMR	PHORMIUM X 'AMAZING RED' / AMAZING RED NEW ZEALAND FLAX	1 GAL	LOW	36" o.c.
			PHO DUE	PHORMIUM X 'DUET' / DUET NEW ZEALAND FLAX	1 GAL	LOW	36" o.c.
			RHA MOU	RHAMNUS CALIFORNICA 'MOUND SAN BRUNO' / MOUND SAN BRUNO COFFEEBERRY	5 GAL	LOW	72" o.c.
			SAL POZ	SALVIA X 'POZO BLUE' / POZO BLUE SAGE	5 GAL	LOW	48" o.c.
<u>SHRUB / GROUNDCOVER AREAS</u>							
4 H8.4			HEL SEM	HELICTOTRICHON SEMPERVIRENS / BLUE OAT GRASS	1 GAL	MED	24" o.c.
			CIS PUL	CISTUS X PULVERULENTUS 'SUNSET' / SUNSET ROCKROSE	5 GAL	LOW	72" o.c.



NOT FOR
CONSTRUCTION

City of
Santa Rosa




CITY OF SANTA ROSA HOWARTH COURTS RENOVATION	SCALE: AS SHOWN		DATE: 1/15/2025
	DWN BY: IC/DC	CHK BY: NR	
PLANTING PLAN	APPROVED: Director — Engineering		
	By _____ Date _____		
	Dan Hennessey		
	No.	Date	
CONTRACT NO. C00714			
SHEET	9	OF	15
FILE NO. 2024-0014			

File Path: N:\Projects\2024\Projects\34623_HowarthAndGawwraCourtRenovation\3_ConstructionDocuments\34623_D1.dwg Plot Date: 2/20/25 Sheet 8 of 20
Copyright © 2024 Colander Associates Landscape Architecture, Inc.

NO.	DATE	REVISION	BY

SCALE: AS SHOWN	DATE: 1/15/2025
DWN BY: IC/DC	CHK BY: NR
APPROVED: Director – Engineering	
By _____	Date _____
Don Hennessey	


CITY OF SANTA ROSA HOWARTH COURTS RENOVATION CONSTRUCTION DETAILS	CONTRACT NO. C00714
	SHEET 10 OF 15
	FILE NO. 2024-0014



1
H8.0

TREE PROTECTION FENCING

PROP-PP-P2911-88



2
H8.0

STORM DRAIN INLET PROTECTION

PROP-PP-P2911-90


File Path: \\projects\2024\Projects\34623_HowarthAndGowinPavedCourtRenovation\3_ConstructionDocuments\34623.DWG Per Date: 2/20/25 Sheet 8 of 20
Copyright © 2024 Callender Associates Landscape Architecture, Inc.

NO.	DATE	REVISION	BY


SCALE: AS SHOWN	DATE: 1/15/2025
DWN BY: IC/DC	CHK BY: NR
APPROVED: Director – Engineering	
By _____	Date _____
Don Hennessey	

CITY OF SANTA ROSA HOWARTH COURTS RENOVATION	CONSTRUCTION DETAILS
---	----------------------

CONTRACT NO. C00714
SHEET 11 OF 15
FILE NO. 2024-0014




1
H8.1
3" = 1'-0"
PROP-PP-P2911-56



2
H8.1
3" = 1'-0"
PROP-PP-P2911-58

NOTE:


1. INSTALL FENCE FABRIC ON THE COURT SIDE OF THE FENCE FRAME.
2. WHEN FENCE IS ADJACENT TO AN EXISTING FENCE THAT IS LESS THAN 10 FEET TALL, THE NEW FENCE SHALL MATCH THE HEIGHT OF THE EXISTING FENCE.
3. SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION.




3
H8.1
3/16" = 1'-0"
PROP-PP-P2911-67

NOTES:

1. THE MAXIMUM FORCE REQUIRED TO PUSH OR PULL OPEN THE GATE SHALL NOT EXCEED 5 POUNDS PER CBC 11B-404.2.9.
2. SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION.




4
H8.1
1/2" = 1'-0"
PROP-PP-P2911-68




5
H8.1
1/2" = 1'-0"
PROP-PP-P2911-69

File Path: I:\Projects\2024\Projects\24003_HowarthAndGwinParksCourtRenovation\3_ConstructionDocuments\24003.DWG Per Date: 2/20/25 Speed By: Dosilio
Copyright © 2024 Calender Associates Landscape Architecture, Inc.




1
H8.2 CHAIN LINK SINGLE GATE, 4' HEIGHT
1/2" = 1'-0" PROP-PP-P2911-71




2
H8.2 CHAIN LINK SINGLE GATE MODIFICATION
1/2" = 1'-0" PROP-PP-P2911-72


	PICKLEBALL	TENNIS
X	3'-0"	3'-6"



5
H8.2 NET, POST, AND CENTER TIE-DOWN
3/4" = 1'-0" PROP-PP-P2911-75




4
H8.2 SITE FURNISHING FOOTING
1" = 1'-0" PROP-PP-P2911-74



3
H8.2 CHAIN LINK FENCE REPAIR
3/8" = 1'-0" PROP-PP-P2911-73

- NOTES:
1. ALL STRIPING IS 2" WIDE, COLOR WHITE.
 2. DIMENSIONS ARE TO THE OUTER EDGE OF STRIPING.



6
H8.2 PICKLEBALL COURT STRIPING
1/8" = 1'-0" PROP-PP-P2911-76


NO.	DATE	REVISION	BY

SCALE: AS SHOWN	DATE: 1/15/2025
DWN BY: IC/DC	CHK BY: NR
APPROVED: Director - Engineering	Date
By: Don Hennessey	



1633 Bayshore Highway, Suite 133
Burlingame, CA 94010
T 650.375.1313
www.collanderassociates.com
CALA Project No. 24023

NOT FOR
CONSTRUCTION




NO.	DATE	REVISION	BY

SCALE: AS SHOWN	DATE: 1/15/2025
DWN BY: IC/DC	CHK BY: NR
APPROVED: Director – Engineering	
By _____ Date _____	
Don Hennessey	

CITY OF SANTA ROSA HOWARTH COURTS RENOVATION	CONSTRUCTION DETAILS
---	----------------------

CONTRACT NO. C00714
SHEET 13 OF 15
FILE NO. 2024-0014


- NOTES:
- ALL STRIPING IS 2" WIDE, COLOR WHITE.
 - DIMENSIONS ARE TO THE OUTER EDGE OF STRIPING.



1
H8.3
TENNIS COURT STRIPING

1/8" = 1'-0"

PROP-PP-P2911-77




2
H8.3
DRIP CONTROL ZONE KIT

1 1/2" = 1'-0"

PROP-PP-P2911-80

- NOTES:
- CENTER VALVE BOX OVER REMOTE CONTROL VALVE TO FACILITATE SERVICING VALVE.
 - SET RCV AND VALVE BOX ASSEMBLY IN GROUND COVER/SHRUB AREAS.
 - SET BOXES PARALLEL TO EACH OTHER AND PERPENDICULAR TO EDGE OF ADJACENT PAVEMENT
 - AVOID HEAVILY COMPACTING SOIL AROUND VALVE BOXES TO PREVENT COLLAPSE AND DEFORMATION OF VALVE BOXES.




3
H8.3
VALVE BOX LAYOUT

1" = 1'-0"

PROP-PP-P2911-78


NOTE: TAPE AND BUNDLE WIRING AT 10'-0" INTERVALS.



4
H8.3
TRENCHING

1 1/2" = 1'-0"

PROP-PP-P2911-79




5
H8.3
DRIP TUBING LATERAL CONNECTION

1 1/2" = 1'-0"

PROP-PP-P2911-81

- NOTES:
- STAKE EMITTER LINE EVERY 4 FEET.
 - LATERAL LINE, FLUSH VALVE AND DRIP REMOTE CONTROL ZONE KIT SHOWN OUTSIDE OF PLANTING AREA FOR GRAPHIC PURPOSES ONLY. LOCATE WITHIN PLANTING AREA WHERE POSSIBLE.



6
H8.3
DRIP LAYOUT - CENTER

1" = 1"


PROP-PP-P2911-82

File Path: I:\Projects\2024\Projects\24023_HowarthAndGwinParksCourtRenovation\3_ConstructionDocuments\24023_01.dwg Plot Date: 2/20/25 Sheet 8 of 20
Copyright © 2024 Callender Associates Landscape Architecture, Inc.

NO.	DATE	REVISION	BY

SCALE: AS SHOWN	DATE: 1/15/2025
DWN BY: IC/DC	CHK BY: NR
APPROVED: <i>Director – Engineering</i>	
By _____ Date _____ Dan Hennessey	

CITY OF SANTA ROSA HOWARTH COURTS RENOVATION	CONSTRUCTION DETAILS	CONTRACT NO. C00714
		SHEET 14 OF 15
		FILE NO. 2024-0014




1
H8.4

DRIP FLUSH VALVE

1 1/2" = 1'-0"

PROP-PP-P2911-84




2
H8.4

DRIP INDICATOR

1" = 1"

PROP-PP-P2911-83




3
H8.4

SHRUB PLANTING

1/4" = 1'-0"

PROP-PP-P2911-86




NOTE:
FOR PLANT SPACING 'X' SEE PLANTING PLAN

4
H8.4

SHRUB / GROUNDCOVER SPACING

1/4" = 1'-0"

PROP-PP-P2911-87



NOTES:

- THIS DETAIL IS TO BE USED FOR THE 10'-0" TALL (MAX) CHAINLINK FENCE
- POSTS ARE TO BE SPACED NO MORE THAN 10'-0"cc, TYP.
- POSTS ARE TO BE SCHEDULE 40 PIPE PER S0.1
- STEEL POSTS ARE TO BE HOT-DIPPED GALVANIZED.

POST & FOOTING
FOR 10' TALL
FENCE

1" = 1'-0"

1

CONCRETE NOTES:

- ALL CONCRETE SHALL BE NORMAL WEIGHT PER ACI 301 AND HAVE PROPORTIONS OF CEMENT, COARSE AND FINE AGGREGATE, WATER AND ADMIXTURES TO PRODUCE THE PROPERTIES SPECIFIED FOR EACH CONCRETE MIX TYPE PER ACI 301 ON THE BASIS OF PREVIOUS FIELD EXPERIENCE AND SUPPORTED BY PREVIOUS TEST RECORDS.
- CONCRETE SHALL HAVE THE FOLLOWING MINIMUM PROPERTIES. REFER TO PROJECT SPECIFICATIONS (WHERE APPLICABLE) FOR ADDITIONAL REQUIREMENTS.

CLASS	APPLICATION	STRENGTH f _c (psi)	MAX W/C Ratio
CLASS A	FOOTINGS	4500	0.45
TEST CONCRETE STRENGTH PER 2022 CBC CH. 17			

- THE APPROVED PROPORTIONS SHALL BE CAREFULLY MAINTAINED. NO DEVIATION FROM THE APPROVED PROPORTIONS SHALL BE MADE WITHOUT WRITTEN APPROVAL BY ENGINEER.
 - USE ADMIXTURES IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. USE WATER-REDUCING ADMIXTURE THAT WILL NOT RESULT IN SEGREGATION, HONEYCOMBING, OR ROCK POCKETS.
 - ANY OF THE ABOVE MIXES CAN BE USED FLOWABLE (8" MAX SLUMP) IF THE PROPER ADDITION OF ADMIXTURES IS INCLUDED AND THE WATER TO CEMENT RATIO IS NOT INCREASED.
 - CEMENT PER ASTM C-150 TYPE I OR II FLY ASH PER ASTM C-618 CLASS N OR CLASS F UP TO 20% OF PORTLAND CEMENT MAY BE SUBSTITUTED WITH FLY ASH
 - COARSE AND FINE AGGREGATES PER ASTM-C-33
 - ADMIXTURES AND DOSAGES WILL VARY WITH CLIMATE AND JOB SITE REQUIREMENTS. CONTRACTOR IS RESPONSIBLE FOR PROVIDING MIX DESIGN SUITABLE FOR JOB SITE CONDITIONS. ADMIXTURES CONTAINING CHLORIDES ARE NOT PERMITTED.
- ALL DEBRIS SHALL BE REMOVED FROM FORMS AND FOOTING EXCAVATIONS PRIOR TO POURING CONCRETE. NO WOOD STAKES OR FORM SPREADERS SHALL BE PERMITTED IN CONCRETE.
 - BALL REINFORCEMENT, ANCHOR BOLTS, AND OTHER EMBEDDED ITEMS SHALL BE SECURED IN POSITION SHOWN ON DRAWINGS PRIOR TO PLACING CONCRETE.
 - CONCRETE SHALL BE CONSOLIDATED BY MECHANICAL VIBRATION PER ACI 309 BY MEANS SUITABLE FOR ON SITE CONDITIONS. USE HAND RODDING OR TAMPING AS REQUIRED.
 - CONSTRUCTION JOINTS SHALL HAVE ALL LOOSE MATERIAL REMOVED AND SHALL BE INTENTIONALLY ROUGHENED TO 1/4" AMPLITUDE PRIOR TO POURING CONCRETE. CONTRACTOR SHALL SUBMIT CONSTRUCTION JOINT LOCATIONS TO ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTION.
 - ALL FORMWORK TO REMAIN IN PLACE FOR DURATION AS REQUIRED BY LATEST EDITION OF ACI 318
 - REFER TO ACI RECOMENDATIONS FOR PLACING AND CURING CONCRETE IN COLD AND HOT WEATHER CONDITIONS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING CONCRETE MIX DESIGN WITH BATCH PLANT TO PROVIDE CONCRETE MIX APPROPRIATE FOR SITE CONDITIONS.
 - CONTRACTOR IS RESPONSIBLE FOR DETERMINING AND IMPLEMENTING APPROPRIATE CURING PROCEDURES FOR ACTUAL SITE/WEATHER CONDITIONS AND SHALL INCLUDE PROVISIONS FOR INCLEMENT WEATHER. REFER TO ACI 308R.
 - ALL SLABS SHALL BE FLAT AND LEVEL W/A TOLERANCE OF 3/16" IN 10' FOR FLATNESS AND MINIMUM LOCAL VALUE F = 32 PER ASTM 1155. THE PROJECT OWNER MAY REJECT ANY CONSTRUCTION THAT DOES NOT MEET THE FLATNESS CRITERIA NOTED WITH REPLACEMENT AT CONTRACTOR'S EXPENSE.
 - CONDUITS AND PIPES EMBEDDED IN THE SLAB (OTHER THAN THOSE PASSING VERTICALLY THROUGH) SHALL NOT BE PERMITTED. CONTRACTOR TO SUBMIT FOOTING PENETRATIONS TO STRUCTURAL ENGINEER FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.

CONCRETE REINFORCEMENT NOTES:

- DETAIL, FABRICATE, AND PLACE REINFORCING PER ACI 315 AND ACI 318. SUPPORT REINFORCEMENT W/APPROVED CHAIRS, SPACERS, OR TIES.
- REINFORCEMENT SHALL BE DEFORMED BILLET STEEL PER ASTM A-615, GRADE 60. ALL REINFORCEMENT AT BOUNDARY ELEMENTS AND REINFORCEMENT TO BE WELDED SHALL BE ASTM A-706, GRADE 60.
- ALL BENDING OF REINFORCEMENT PER ACI. FIELD BENDING OF REINFORCEMENT SHALL NOT BE PERMITTED.
- REINFORCEMENT IN WALLS, SLABS, BEAMS AND FOOTINGS SHALL BE CONTINUOUS AROUND CORNERS OR CORNER BARS PROVIDED.
- LAP ALL REINFORCEMENT 48DB FOR #6 AND SMALLER BARS, 60DB FOR #7 AND LARGER BARS. INCREASE LAP LENGTH 30% WHERE MORE THAN 12" OF FRESH CONCRETE IS POURED UNDER REINFORCEMENT.
- TRIM REINFORCING AROUND OPENINGS SHALL BE A MINIMUM 2-#6 TOP AND BOTTOM EXTENDING 40" BEYOND OPENING AT EACH CORNER. PROVIDE 90° HOOK AT CORNERS WHERE STRAIGHT EMBEDMENT NOT POSSIBLE.
- REINFORCING SHALL BE TIED IN PLACE. TACK WELDING OF REINFORCING IS NOT PERMITTED.
- CONTRACTOR TO TAKE NECESSARY PRECAUTIONS TO INSURE CONCRETE IS PROPERLY CONSOLIDATED AROUND ALL BOLTS, ANCHORAGES, ETC.
- WHERE REINFORCING IS NOT SPECIFIED, REFER TO ACI 318 FOR MINIMUM REINFORCEMENT.
- WELDED WIRE FABRIC PER ASTM A-185 AND ASTM A-82.
- DEFORMED BAR ANCHORS PER ASTM A-496
- PROVIDE MINIMUM COVER FOR ALL REINFORCING AS FOLLOWS:

APPLICATION	COVER
CONCRETE CAST AGAINST EARTH	3"
CONCRETE EXPOSED TO EARTH OR WEATHER: #5 AND SMALLER	1 1/2"
#6 AND LARGER	2"
CONCRETE NOT EXPOSED TO EARTH OR WEATHER: SLABS AND WALLS	3/4"
BEAMS AND COLUMNS	1 1/2"

- STAGGER LAPS IN ADJACENT BARS 6'-0" MINIMUM
- PROVIDE FOOTING DOWELS TO MATCH SIZE AND SPACING OF VERTICAL REINFORCEMENT UNO
- ALL REINFORCING TO BE WELDED SHALL BE ASTM A-706 AND CONTINUOUSLY INSPECTED AND PERFORMED PER AWS STANDARDS.
- REINFORCING WHICH IS TO BE DOWELED INTO EXISTING CONCRETE SHALL BE INSTALLED W/SIMPSON AT-XP PER IAPMO ER-263 UNO

TESTS & INSPECTIONS:

TESTS & INSPECTIONS SHALL BE PROVIDED BY A QUALIFIED TESTING AGENCY AS NOTED BLW AND SHALL CONFORM TO THE REQUIREMENTS OF 2022 CBC, SECTION 1701

CONCRETE:

- INSPECT ANCHORS CAST IN CONCRETE
- INSPECT POST-INSTALLED ANCHORS
 - ADHESIVE ANCHORS INSTALLED IN HORIZINTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS
 - ALL OTHER MECHANICAL AND ADHESIVE ANCHORS
- REINFORCING STEEL AND PLACEMENT
- VERIFYING MIX DESIGN

Inspections
Continuous ☐
Periodic ☐

SOILS:

- FOOTING EXCAVATIONS AND BEARING
- CLASSIFICATION AND TESTING OF FILL
- FILL PLACEMENT AND COMPACTION
- SUBGRADE PREPARATION
- CIP PIERS AND PILES
 - OBSERVE DRILLING OPERATIONS
 - LOCATIONS, DIMENSIONS, EMBEDMENT
 - CND BEARING

☐ ☒ ☐ ☒

FOUNDATION NOTES:

- FOUNDATIONS ARE DESIGNED IN ACCORDING TO THE PROJECT GEOTECHNICAL REPORT 7394.004.PW.1 FOR HOWARTH COMMUNITY PARK.

DRILLED PIER FOUNDATIONS

PROPERTY	VALUE
ALLOWABLE SKIN FRICTION	300 PSF
LATERAL PRESSURE	150 PCF

- FOOTINGS SHALL BEAR ON FIRM, DRY, UNDISTURBED SOIL OR COMPACTED FILL PER SOILS REPORT. FOOTING DEPTHS INDICATED ON THE PLANS ARE MINIMUM. AREAS OVER-EXCAVATED SHALL BE BACKFILLED W/COMPACTED STRUCTURAL FILL PER SOILS REPORT OR LEAN CONCRETE (FC=1000 PSI) AT CONTRACTOR'S EXPENSE.
- CONTRACTOR TO NOTIFY ENGINEER OF RECORD IMMEDIATELY WHERE JOB SITE CONDITIONS ARE DIFFERENT THAN SHOWN ON CONTRACT DOCUMENTS.
- ALL FOOTINGS NOT FORMED SHALL BE POURED INTO NEAT EXCAVATIONS. PRECAUTIONS SHALL BE TAKEN TO PREVENT SLOUGHING OF SOIL INTO THE FOOTING EXCAVATION PRIOR TO AND DURING THE PLACEMENT OF CONCRETE.

STRUCTURAL STEEL NOTES:

- THE FABRICATION AND ERECTION OF ALL STEEL CONSTRUCTION SHALL CONFORM TO THE 2022 CBC AND THE AISC STEEL CONSTRUCTION MANUAL 16th EDITION.
- STRUCTURAL STEEL SHAPES SHALL CONFORM TO THE FOLLOWING

2.1	CHANNELS	ASTM A36, Fy = 36 KSI
2.2	ANGLES	ASTM A36, Fy = 36 KSI
2.3	BARNS AND PLATES	ASTM A36, Fy = 36 KSI
2.4	PIPE	SCHEDULE 40 - ASTM A53, GRADE B TYPE E OR S, Fy = 30 KSI (MIN)
2.5	RECTANGULAR HSS	ASTM A500, GRADE B, Fy = 46 KSI
2.6	ROUND HSS	ASTM A500, GRADE B, Fy = 46 KSI

- WELDING SHALL BE BY THE ELECTRIC ARC PROCESS (SHIELDED METAL ARC WELDING, FLUX CORE ARC WELDING, GAS METAL ARC WELDING) PER AWS STANDARDS AND BY CERTIFIED WELDERS. REFER TO "QUALIFICATION PROCEDURE" AWS D1.1.
- ALL WELDED JOINTS AND ELECTRODES ARE TO BE "PREQUALIFIED." ALL WELDING ELECTRODES ARE TO BE E70XX UNO. FCAW FILLER METAL WIRE SHALL BE 3/32" MAX DIAMETER AND SMAW FILLER METAL WIRE SHALL BE 3/32" MAX DIAMETER.
- ALL STRUCTURAL STEEL SHALL BE ERECTED PLUM AND TRUE TO LINE. TEMPORARY BRACING SHALL BE INSTALLED AS REQUIRED TO MAINTAIN STABILITY OF THE STRUCTURE UNTIL THE STRUCTURAL SYSTEM IS SUBSTANTIALLY COMPLETE.
- ALL STRUCTURAL STEEL ITEMS EMBEDDED IN CONCRETE AND LOCATED BELOW GRADE SHALL HAVE 3" MINIMUM COVER. ALL STRUCTURAL STEEL ITEMS EMBEDDED IN CONCRETE AND LOCATED ABOVE GRADE AT CONCRETE EXPOSED TO WEATHER SHALL HAVE 1 1/2" MINIMUM COVER.
- ALL STEEL BOLTS ARE TO HAVE STANDARD GAGE AND PITCH PER AISC. ALL STEEL-TO-STEEL BOLTED CONNECTIONS SHALL BE WITH A325-N BOLTS. UNO. ALL EMBEDDED ANCHOR BOLTS SHALL BE F1554 GRADE 36 UNO. HOLES AT STEEL-TO-STEEL CONNECTIONS ARE TO BE 1/8" OVERSIZE AND HOLES AT STEEL COLUMN BASE PLATES ARE TO BE 3/8" OVERSIZE, UNO.
- STRUCTURAL STEEL IS TO BE SHOP PRIMED WITH ONE COAT, EXCEPT THE BELOW NOTED LOCATIONS, WHERE PRIMER SHALL BE HELD 2" CLEAR:
 - STEEL SURFACES EMBEDDED IN CONCRETE
 - SURFACES TO BE FIELD WELDED
 - CONTACT SURFACES WITH HIGH STRENGTH BOLTED CONNECTIONS

- ALL STRUCTURAL COLUMNS ARE TO BE SET UPON ANCHOR RODS WITH LEVELING NUTS ALLOWING APPROXIMATELY 1 1/2" ± CLEARANCE. CLEARANCE SPACE UNDER COLUMNS AND BLOCK-OUTS IN CURBS FOR COLUMN PLACEMENT ARE TO BE FILLED WITH A NON-SHRINK, HIGH-STRENGTH, POURABLE GROUT.



2-21-25

STRUCTURAL SHEET INDEX:

S0.1 STRUCTURAL TYPICAL NOTES & DETAIL

ABBREVIATIONS:


@	AT	LS	LAG SCREW
AB	ANCHOR BOLT		
approx	APPROXIMATE	MAX	MAXIMUM
Arch	ARCHITECT/URAL	MFGR	MANUFACTURER
BC	BOTTOM CHORD	MIN	MINIMUM
BLK	BLOCK OR BLOCKING	(N)	NEW
BO	BOTTOM OF	#	NUMBER
CBC	CALIFORNIA BUILDING CODE	NTS	NOT TO SCALE
oc	ON CENTER	OD	OUTSIDE DIAMETER
CIP	CAST IN PLACE	OH	OPPOSITE HAND
CJ	CONSTRUCTION JOINT	OV	OVER
CL	CENTER LINE	PL	PLATE
CMU	CONCRETE MASONRY UNIT	PT	PRESSURE TREATED
CONC	CONCRETE	REIN	REINFORCEMENT
CONT	CONTINUOUS	SIM	SIMILAR
DF	DOUGLAS FIR	SP	STRUCTURAL PANEL
Ø	DIAMETER	SW	SHEAR WALL
DL	DEAD LOAD	T&B	TOP AND BOTTOM
DT	DRAFT TRUSS	T&G	TONGUE AND GROOVE
(E)	EXISTING	thru	THROUGH
EN	EDGE NAIL	TN	TOE NAIL
EOR	ENGINEER OF RECORD	TOS	TOP OF STEEL
FDN	FOUNDATION	TYP	TYPICAL
FF	FINISH FLOOR		
FO	FACE OF	W/O	WITHOUT
	FOOT/FEET	VIF	VERIFY IN FIELD
FTG	FOOTING	W/O	WITHOUT
FRMG	FRAMING	WWF	WELDED WIRE FABRIC
GLB	GLUE LAMINATED BEAM		
HD	HOLD DOWN		
HGD	HOT-DIPPED GALVANIZED		
HDR	HEADER		

GENERAL NOTES:


- ALL CONSTRUCTION SHALL CONFORM TO 2022 CBC W/AMENDMENTS AND ALL OTHER APPLICABLE CODES AND REGULATIONS.
- NOTES ON THIS SHEET ARE TYPICAL AND SHALL APPLY UNLESS OTHERWISE NOTED OR SHOWN. TYPICAL DETAILS SHALL APPLY FOR ALL LIKE CONDITIONS UNLESS OTHERWISE NOTED OR DETAILED.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS, ELEVATIONS, EXISTING CONDITIONS, AND OTHER RELATED ITEMS. THE CONTRACTOR SHALL REVIEW THE CONTRACT DOCUMENTS PRIOR TO CONSTRUCTION AND SHALL NOTIFY THE ENGINEER OF RECORD IF ANY CONFLICTS ARE SHOWN OR NOTED.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONFORM TO RELEVANT SECTIONS OF THE CALIFORNIA "CONSTRUCTION SAFETY ORDERS" AND ALL OSHA REQUIREMENTS. THE ENGINEER OF RECORD ACCEPTS NO RESPONSIBILITY FOR THE CONTRACTOR'S FAILURE TO COMPLY W/ THESE REQUIREMENTS.
- DESIGN AND CONSTRUCTION OF ALL TEMPORARY BRACING, SHORING, FORMING, ETC REQUIRED SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- OVERALL DIMENSIONS ARE SHOWN TO FACE OF STUD OR CONCRETE UNLESS NOTED OTHERWISE.

DRAWING STANDARDS:


SHEET NUMBERING



SYMBOLS



MATERIAL LEGEND



DESIGN CRITERIA:

- PROJECT ADDRESS: HOWARTH MEMORIAL COMMUNITY PARK 630 SUMMERFIELD, SANTA ROSA

- BUILDING CODE: 2022 CALIFORNIA BUILDING CODE

- LATERAL LOADS: RISK CATEGORY I

WIND LOADS
BASIC WIND SPEED 86 MPH (LRFD), 66 MPH (ASD)
EXPOSURE C

SEISMIC LOADS
SITE CLASS D
SEISMIC DESIGN CATEGORY D
IMPORTANCE FACTOR 1.00
REDUNDANCY, RHO 1.00
R = 1.25
S_s = 2.539
S_i = 0.988
S_{ps} = 1.693
S_{p1} = NA
V = 1.625W(USD); 1.138W(ASD)

RW CONSULTING
Engineers Inc
1450 HARBOR BLVD, SUITE F
WEST SACRAMENTO, CA 95691
(916)229-8345 ph
dhayes@rwengineers.com

City of
Santa Rosa

DATE: 02/21/25

SCALE: AS SHOWN

CITY OF SANTA ROSA

CHK BY: DH

DWN BY: DH

HOWARTH COURTS RENOVATION

APPROVED: Director - Engineering

By: Dan Hennessey

STRUCTURAL TYPICAL
NOTES AND DETAIL

REVISION

NO.

DATE

CONTRACT NO.
C00714

SHEET 15 OF 15

FILE NO. 2024-0014