





ZONING LEGEND

IL - LIGHT INDUSTRIAL
BP - BUSINESS PARK


CG - GENERAL COMMERCIAL
MMU - MAKER MIXED USE

NMU - NEIGHBORHOOD MIXED USE
R-3 - MULTI-FAMILY RESIDENTIAL

SITE PLAN - ZONING



COUNTY ASSESSOR PARCEL MAP



VICINITY MAP

City of Santa Rosa
Planning & Economic
Development Department
03/28/2023
RECEIVED


MPM
ARCHITECTS

SONOMA STRENGTH ACADEMY

1125 BRIGGS AVE
SANTA ROSA, CA 95401



A100
VICINITY MAP
AND ZONING
03.21.2023




1 SITE PLAN - CONCEPT
A101 1/8" = 1'-0"




	PARKING COUNTS	KEYNOTE LEGEND
	PER CITY OF SANTA ROSA ZONING CODE 20-36.040 NUMBER OF PARKING SPACES REQUIRED C. EXPANSION OF STRUCTURE, CHANGE OF USE 2. CHANGE IN USE. WHEN A BUILDING'S USE CHANGES TO A NEW USE, FOR EXAMPLE A RETAIL USE TO A RESTAURANT, WITHOUT ENLARGING THE SPACE IN WHICH THE USE IS LOCATED, THERE SHALL BE NO ADDITIONAL PARKING REQUIRED FOR THE NEW USE, EXCEPT THAT THE NEW USE SHALL COMPLY WITH CURRENT ADA STANDARDS FOR PARKING, PROVIDED THAT ANY DEFICIENCY IN PARKING IS NO MORE THAN 10 SPACES, OR A 25 PERCENT OVERALL REDUCTION FROM STANDARD PARKING REQUIREMENTS, WHICHEVER IS GREATER.	11 (E) SPACES REPLACED BY SPACES CONFORMING TO CITY OF SANTA ROSA ZONING CODE. STANDARD STALLS 4 PARALLEL STALLS 6 ACCESSIBLE VAN ACCESSIBLE 1 TOTAL 11 PROVIDED BICYCLE PARKING 1/4000SF = 4900/4000=1.225 2 PROVIDED
		G00.02 (E) BUILDING TO REMAIN G00.04 (E) DRIVEWAY TO REMAIN G00.05 (E) CONCRETE PAD TO REMAIN. G00.10 APPROXIMATE PROPERTY LINE G00.11 (E) CHAIN LINK GATE TO REMAIN G20.01 VAN ACCESSIBLE PARKING SPACE PER SANTA ROSA CITY ZONING STANDARDS AND CBC CHAPTER 11B G20.03 FUTURE EXTERIOR EXERCISE STATIONS G20.04 PARALLEL PARKING SPACE PER CITY OF SANTA ROSA ZONING STANDARDS G20.05 STANDARD PARKING SPACE PER CITY OF SANTA ROSA ZONING STANDARDS G20.06 (N) BICYCLE RACK. PROVIDED MINIMUM OF 2 BICYCLE SPACES G20.07 STEEL BOLLARD, TYPICAL AT ALL STANDARD PARKING STALLS G20.08 VAN ACCESSIBLE PARKING SIGN PER CBC 11B-502.6 G20.09 TRUNCATED DOMES PER CBC 11B-705.1 G30.01 (E) PG&E TRANSFORMER PAD TO REMAIN





NOTE: SECOND FLOOR STORAGE ABOVE RECEPTION AND OFFICE. NO WORK PROPOSED ON SECOND FLOOR

BRIGGS AVE



CONCEPTUAL FLOOR PLAN